

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2021-22/OW/WORK_INDENT50345/CALL-2

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/16/2021-22, Date: 15-03-2022

Name of Work: Construction of culverts in Amruthalli and surrounding areas in ward no.07 byatarayanapura (Call-2)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				MAHESH C (K R CONSTRUCTIONS..)	
				In Figures	In Words
1	119.52	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.	cum	80.0	Rupees Eighty Only
2	32.76	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials labour, HOM curing, form works, scaffolding and centering complete as per specification	cum	5500.0	Rupees Five Thousand Five Hundred Only
3	63.18	Providing and constructing granite /trap/basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at two m apart in each course including cost of materials, labour, curing etc., complete as per specifications	cum	4500.0	Rupees Four Thousand Five Hundred Only
4	28.08	Providing and laying cement concrete of mix 1:2:4 with OPC @ 240 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.63cum and fine aggregates @0.42 cum including cost of materials, labour, HOM curing, form works scaffolding and centering complete as per MORTH section	cum	6000.0	Rupees Six Thousand Only
5	117	Providing and fixing 20 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick well compacted cost of all materials labour curing complete as per specification	sqm	3579.0	Rupees Three Thousand Five Hundred Seventy Nine Only
6	119.52	Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1: Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification	cum	82.08	Rupees Eighty Two and Eight Paise Only

Signature of the Contractor

[Signature]
 Executive Engineer
 Byarayanapura Division
 BBMP, Bangalore - 92

[Signature]
 28/04